
Sural Nerve Conduction Interpretation Guide

This guide is for informational purposes only. It does not provide a clinical diagnosis.



Severity	Amplitude	CV
Normal	Normal	Normal
Mild	Normal	Abnormal
Moderate	Abnormal	Normal or Abnormal
Severe	Undetectable	

^{*}Data on file

Error Code Key[†]

Display	Light	Description
LЬ	•	Incorrect limb selected
Pn	•	Data quality issue requiring retest
Pr	•	Stimulation issue. Possible causes: Insufficient gel on probes Poor probe contact with skin Inadequate skin preparation Probe movement during test Gel smearing between probes
5n	0	Incorrect biosensor insertion or defective biosensor
5n	•	Data quality issue. Possible causes: Biosensor backing not removed Incomplete biosensor contact Skin inadequately prepared
Ес	•	Data quality issue. Possible causes: • Excessive muscle contraction or patient movement • Biosensor backing not removed
٥٢	•	Patient ankle too cold
Lo	•	Low battery
На	•	Device hardware issue
ЦЬ	•	Excessive biosensor reuse detected, device is disabled

[†]Please refer to the Reference Guide for a detailed list of causes and solutions.